

MERCER COUNTY SCD REQUIRED SOIL EROSION AND SEDIMENT CONTROL NOTES

- 1. THE MERCER COUNTY SOIL CONSERVATION DISTRICT SHALL BE NOTIFIED 48 HOURS PRIOR TO STARTING LAND DISTURBANCE ACTIVITY. NOTICE MAY BE MAILED, FAXED OR EMAILED TO: MDCSD, 508 HUGHES DRIVE, HAMILTON SQUARE, NJ 08690... 2. IF APPLICABLE TO THIS PROJECT, THE OWNER SHOULD BE AWARE OF HIS OR HER OBLIGATION TO FILE FOR A NJDES CONSTRUCTION ACTIVITY STORMWATER 563 PERMIT... 3. THE MERCER COUNTY SOIL CONSERVATION DISTRICT SHALL BE NOTIFIED OF ANY CHANGES IN OWNERSHIP... 4. ANY CHANGES TO THE CERTIFIED SOIL EROSION AND SEDIMENT CONTROL PLAN, INCLUDING AN INCREASE IN THE LIMIT OF DISTURBANCE, WILL REQUIRE THE SUBMISSION OF REVISED SOIL EROSION AND SEDIMENT CONTROL PLANS TO THE DISTRICT FOR RE-CERTIFICATION... 5. A COPY OF THE CERTIFIED SOIL EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON SITE AT ALL TIMES... 6. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCES... 7. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CURRENT STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NJ LANGUAGE CONTAINED WITHIN ANY OTHER PERMIT FOR THIS PROJECT IS MORE RESTRICTIVE THAN (BUT NOT CONTRADICTORY TO) WHAT IS CONTAINED WITHIN THESE NOTES OR ON THE CERTIFIED SOIL EROSION AND SEDIMENT CONTROL PLAN... 8. THE STANDARD FOR STABILIZED CONSTRUCTION ACCESS REQUIRES THE INSTALLATION OF A 1 1/2" TO 2 1/2" CLEAN STONE TRACKING PAD AT ALL CONSTRUCTION DRIVEWAYS IMMEDIATELY AFTER INITIAL SITE DISTURBANCE... 9. A SUB-BASE COURSE SHALL BE APPLIED IMMEDIATELY FOLLOWING ROUGH GRADING AND INSTALLATION OF IMPROVEMENTS IN ORDER TO STABILIZE STREETS, ROADS, DRIVEWAYS AND PARKING AREAS... 10. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 14 DAYS AND NOT SUBJECT TO CONSTRUCTION ACTIVITY WILL IMMEDIATELY RECEIVE TEMPORARY STABILIZATION... 11. ANY STEEP SLOPES (I.E. SLOPES GREATER THAN 3:1) RECEIVING PIPELINE OR UTILITY INSTALLATION WILL BE BACKFILLED AND STABILIZED FIRST... 12. PERMANENT VEGETATION SHALL BE SEEDED OR SODDED ON ALL EXPOSED AREAS WITHIN TEN (10) DAYS AFTER FINAL GRADING AND TOPSOILING... 13. AT THE TIME WHEN THE SITE PREPARATION FOR PERMANENT VEGETATIVE STABILIZATION IS GOING TO BE ACCOMPLISHED, ANY SOIL THAT WILL NOT PROVIDE A SUITABLE ENVIRONMENT TO SUPPORT ADEQUATE VEGETATIVE GROUND COVER... 14. DURING THE COURSE OF CONSTRUCTION, SOIL COMPACTION MAY OCCUR WITHIN HAUL ROUTES, STAGING AREAS AND OTHER PROJECT AREAS... 15. PRIOR TO SEEDING, TOPSOIL SHALL BE WORKED TO PREPARE A PROPER SEEDBED... 16. IN ACCORDANCE WITH THE STANDARD FOR MANAGEMENT OF HIGH ACID PRODUCING SOILS... 17. MULCHING TO THE STANDARDS IS REQUIRED FOR OBTAINING A CONDITIONAL REPORT OF COMPLIANCE... 18. HYDROSEEDING IS A TWO-STEP PROCESS... 19. THE CONTRACTOR IS RESPONSIBLE FOR KEEPING ALL ADJACENT ROADS CLEAN DURING LIFE OF THE CONSTRUCTION PROJECT... 20. THE DEVELOPER SHALL BE RESPONSIBLE FOR REMEDIATING ANY EROSION OR SEDIMENT PROBLEMS THAT ARISE AS A RESULT OF ONGOING CONSTRUCTION... 21. CONDUIT OUTLET PROTECTION MUST BE INSTALLED AT ALL REQUIRED OUTFALLS PRIOR TO THE DRAINAGE SYSTEM BECOMING OPERATIONAL... 22. ALL DETENTION / RETENTION BASINS MUST BE FULLY CONSTRUCTED... 23. THE RIDING SURFACE OF ALL UTILITY TRENCHES WITHIN PAVED AREAS SHALL BE 3/4" CLEAN STONE OR BASE PAVEMENT UNTIL SUCH TIME AS FINAL PAVEMENT HAS BEEN INSTALLED... 24. ALL CONSTRUCTION DEWATERING (TRENCHES, EXCAVATIONS, ETC) MUST BE DONE THROUGH AN INLET FILTER AND OUTLET FILTER... 25. ALL SWALES OR CHANNELS THAT WILL RECEIVE RUNOFF FROM PAVED SURFACES MUST BE PERMANENTLY STABILIZED PRIOR TO THE INSTALLATION OF PAVEMENT... 26. NJSA 4:24-39 ET SEQ. REQUIRES THAT NO CERTIFICATE OF OCCUPANCY OR TEMPORARY CERTIFICATE OF OCCUPANCY BE ISSUED BY THE MUNICIPALITY BEFORE THE PROVISIONS OF THE CERTIFIED SOIL EROSION AND SEDIMENT CONTROL PLAN HAVE BEEN SATISFIED... 27. MONITORING OF AREAS WHERE HIGH ACID PRODUCING SOIL HAS BEEN PLACED OR BURIED SHOULD BE PERFORMED FOR AT LEAST 2 YEARS OR LONGER IF PROBLEMS OCCUR...

PERMANENT STABILIZATION WITH SOD

PERMANENT SODDING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY. THE FOLLOWING SOD SCHEDULE SHOULD BE USED FOR PERMANENT STABILIZATION:

- 1. SITE PREPARATION
A. GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR LIMING, FERTILIZING, INCORPORATION OF ORGANIC MATTER, AND OTHER SOIL PREPARATION PROCEDURES...
2. SOIL PREPARATION
A. FERTILIZER SHALL BE APPLIED AT A RATE OF 500 POUNDS PER ACRE OR 11 POUNDS PER 1,000 SQUARE FEET USING 10-10-10 OR EQUIVALENT WITH 50% WATER INSOLUBLE NITROGEN...
3. SOD PLACEMENT
A. SOD STRIPS SHOULD BE LAID ON THE CONTOUR, NEVER UP AND DOWN THE SLOPE...
4. TOPDRESSING
A. SINCE SOIL ORGANIC MATTER AND SLOW RELEASE NITROGEN FERTILIZER (WATER INSOLUBLE) ARE PRESCRIBED IN SECTIONS 1 AND 2...
5. MULCHING
A. MULCHING IS REQUIRED ON ALL SEEDING TO INSURE AGAINST EROSION BEFORE GRASS IS ESTABLISHED...
6. TOPDRESSING
A. SINCE SOIL ORGANIC MATTER AND SLOW RELEASE NITROGEN FERTILIZER (WATER INSOLUBLE) ARE PRESCRIBED IN SECTIONS 1 AND 2...

Table with 3 columns: Soil Texture, Tons/Acre, LBS./1,000 SQ. FT.
Rows include Clay, clay loam, and high organic soil; Sandy loam, loam, silt loam; Loomy sand, sand.

TEMPORARY VEGETATIVE COVER FOR SOIL STABILIZATION

DISTURBED AREAS SHALL BE MAINTAINED IN A ROUGH GRADED CONDITION AND TEMPORARILY SEEDED AND HAY MULCHED UNTIL PROPER WEATHER EXISTS FOR THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER... THE FOLLOWING SCHEDULE SHALL BE USED FOR TEMPORARY STABILIZATION:

- 1. SITE PREPARATION
A. INSTALL EROSION CONTROL MEASURES AS INDICATED ON THE "SOIL EROSION AND SEDIMENT CONTROL PLAN," DRAWING CE-101 AND AS DETAILED ON DRAWING CE-502...
2. SEEDBED PREPARATION
A. APPLY GROUND LIMESTONE AND FERTILIZER...
3. SEEDING
A. APPLY PERENNIAL RYEGRASS AT A RATE OF 1 LB/1,000 SF (100 LBS/ACRE) TO A DEPTH OF 2" TO 3"...
4. MULCHING
A. MULCHING IS REQUIRED ON ALL SEEDING TO INSURE AGAINST EROSION BEFORE GRASS IS ESTABLISHED...
5. TOPDRESSING
A. SINCE SOIL ORGANIC MATTER AND SLOW RELEASE NITROGEN FERTILIZER (WATER INSOLUBLE) ARE PRESCRIBED IN SECTIONS 1 AND 2...

STANDARD FOR TOPSOILING

TOPSOIL SHALL BE USED WHERE SOILS ARE TO BE DISTURBED AND WILL BE REVEGETATED. THE FOLLOWING SCHEDULE SHALL BE USED FOR MAINTENANCE OF VEGETATION:

- 1. MATERIALS
A. TOPSOIL SHOULD BE FRIABLE, LOAMY, FREE OF DEBRIS, OBJECTIONABLE WEEDS AND STONES...
2. STRIPPING AND STOCKPILING
A. FIELD EXPLORATION SHOULD BE MADE TO DETERMINE WHETHER QUANTITY AND/OR QUALITY OF SURFACE SOIL JUSTIFIES STRIPPING...
3. SITE PREPARATION
A. GRADE AT THE ONSET OF THE OPTIMAL SEEDING PERIOD TO AS TO MINIMIZE THE DURATION AND AREA OF EXPOSURE OF DISTURBED SOIL TO EROSION...
4. APPLYING TOPSOIL
A. TOPSOIL SHOULD BE HANDLED ONLY WHEN IT IS DRY ENOUGH TO WORK WITHOUT DAMAGING SOIL STRUCTURE...

STANDARD FOR TOPSOILING

STABILIZATION WITH MULCH ONLY

NON-GROWING STABILIZATION MEASURES SHALL BE USED WHERE THE SEASON & OTHER CONDITIONS MAY NOT BE SUITABLE FOR GROWING AN EROSION RESISTANT COVER OR WHERE STABILIZATION IS NEEDED FOR A SHORT PERIOD UNTIL MORE SUITABLE PROTECTION CAN BE APPLIED...

- 1. SITE PREPARATION
A. INSTALL EROSION CONTROL MEASURES AS INDICATED ON THE "SOIL EROSION AND SEDIMENT CONTROL PLAN," DRAWING CE-101 AND AS DETAILED ON DRAWING CE-502...
2. PROTECTIVE MATERIALS
A. APPLY UNROTTED SMALL-GRAIN STRAW, OR SALT HAY UNIFORMLY AT A RATE OF 90 TO 115 LBS./1,000 SF...
3. MULCH ANCHORING
A. ANCHORING SHALL BE ACCOMPLISHED IMMEDIATELY AFTER PLACEMENT TO MINIMIZE LOSS BY WIND OR WATER...
4. SEEDING
A. SEED GERMINATION SHALL HAVE BEEN TESTED WITHIN 12 MONTHS OF THE PLANTING DATE...

STABILIZATION WITH MULCH

CONSTRUCTION OPERATIONS

Table with 2 columns: OPERATION, ANTICIPATED DURATION. Lists various construction activities like site prep, grading, seeding, and mulching with their expected durations from 4 weeks to 1.5 years.

MAINTENANCE OF VEGETATION

MAINTENANCE SHALL OCCUR ON A REGULAR BASIS, CONSISTENT WITH FAVORABLE PLANT GROWTH, SOIL, AND CLIMATIC CONDITIONS. MAINTENANCE SHOULD INCLUDE WORK FOR MOWING, FERTILIZING, LIMING, WATERING, PRUNING, FIRE CONTROL, WEED AND PEST CONTROL, RESEEDING, AND TIMELY REPAIRS...

- 1. THE SITE'S VEGETATED AREAS WILL REQUIRE MEDIAN TO LOW LEVELS OF MAINTENANCE. MOWING IS EXPECTED TO BE INFREQUENT TO PERMIT NATURAL SUCCESSION...
2. FERTILIZER AND LIME SHALL BE APPLIED AS NEEDED TO MAINTAIN A DENSE STANDARD OF DESIRABLE SPECIES...
3. LIME REQUIREMENT SHALL BE DETERMINED BY SOIL TESTING EVERY 2 TO 3 YEARS...
4. WEED INVASION MAY RESULT FROM ABUSIVE MOWING AND FROM INADEQUATE FERTILIZING AND LIMING...
5. VEGETATION SHALL BE KEPT PEST AND DISEASE FREE...
6. ACCUMULATED DRY VEGETATION SHALL BE REMOVED TO REDUCE THE FIRE HAZARD...
7. PRUNE TREES AND SHRUBS TO REMOVE DEAD OR DAMAGED BRANCHES...

MAINTENANCE OF VEGETATION

MERCER COUNTY SOIL CONSERVATION DISTRICT
508 HUGHES DRIVE
HAMILTON SQUARE, N.J. 08690
PHONE: (609) 586-9603
FAX: (609) 586-1117
MERCERSOIL@AOL.COM

CONTRACTOR MUST NOTIFY DISTRICT 48-HOURS PRIOR TO START OF CONSTRUCTION.

SOIL EROSION CONTACT

PERMANENT VEGETATIVE COVER FOR SOIL STABILIZATION (SHOWN FOR REFERENCE ONLY - ALL LAWN AREAS SHALL BE STABILIZED WITH SOD)

PERMANENT SEEDING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE "STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY," THE FOLLOWING SEEDING SCHEDULE SHOULD BE USED FOR PERMANENT STABILIZATION:

- 1. SITE PREPARATION
A. GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING...
2. SEEDBED PREPARATION
A. UNIFORMLY APPLY GROUND LIMESTONE AND FERTILIZER TO TOPSOIL WHICH HAS BEEN SPREAD AND FIRMED...
3. SEEDING
A. SEED GERMINATION SHALL HAVE BEEN TESTED WITHIN 12 MONTHS OF THE PLANTING DATE...
4. MULCHING
A. MULCHING IS REQUIRED ON ALL SEEDING TO INSURE AGAINST EROSION BEFORE GRASS IS ESTABLISHED...
5. IRRIGATION
A. IF SOIL IS MOISTURE DEFICIENT, AND MULCH IS NOT USED, SUPPLY NEW SEEDLINGS WITH ADEQUATE WATER...
6. TOPDRESSING
A. SLOW RELEASE NITROGEN FERTILIZER (WATER INSOLUBLE) IS PRESCRIBED IN 2.A. ABOVE, NON FOLLOW-UP OF TOPDRESSING IS MANDATORY...

PERMANENT SOD

TEMPORARY SEED MIX

STABILIZATION WITH MULCH

MANAGEMENT OF HIGH ACID PRODUCING SOIL

- HIGH ACID PRODUCING SOILS MAY BE PRESENT IN UNDISTURBED SOILS AT VARYING DEPTHS INCLUDING SURFACE AND SUBSURFACE... METHODS AND MATERIALS:
1. LIMIT THE EXCAVATION AREA AND EXPOSURE TIME WHEN HIGH ACID PRODUCING SOILS ARE ENCOUNTERED...
2. TOPSOIL STRIPPED FROM THE SITE SHALL BE STORED SEPARATELY FROM TEMPORARY STOCKPILED HIGH ACID PRODUCING SOILS...
3. STOCKPILES OF HIGH ACID PRODUCING SOIL SHOULD BE LOCATED ON LEVEL LAND TO MINIMIZE ITS MOVEMENT...
4. TEMPORARILY STOCKPILED HIGH ACID PRODUCING SOIL MATERIAL TO BE EXPOSED MORE THAN 30 DAYS SHOULD BE COVERED WITH PROPERLY ANCHORED, HEAVY GRADE SHEETS OF POLYETHYLENE...
5. HIGH ACID PRODUCING SOILS WITH A PH OF 4 OR LESS, OR CONTAINING IRON SULFIDE...
6. AREAS WHERE TREES OR SHRUBS ARE TO BE PLANTED SHALL BE COVERED WITH A MINIMUM OF 24 INCHES OF SOIL WITH A PH OF 5 OR MORE...
7. NON VEGETATIVE EROSION CONTROL PRACTICES (STONE TRACKING PADS, STRATEGICALLY PLACED LIMESTONE CHECK DAM, SILT FENCE, WOOD CHIPS) SHOULD BE INSTALLED TO LIMIT MOVEMENT OF HIGH ACID PRODUCING SOILS FROM AROUND OR OFF THE SITE...
8. FOLLOWING BURIAL OR REMOVAL OF HIGH ACID PRODUCING SOIL, TOPSOILING AND SEEDING OF THE SITE, MONITORING SHOULD CONTINUE FOR APPROXIMATELY 6 TO 12 MONTHS...
9. MONITORING OF AREAS WHERE HIGH ACID PRODUCING SOIL HAS BEEN PLACED OR BURIED SHOULD BE PERFORMED FOR AT LEAST 2 YEARS OR LONGER IF PROBLEMS OCCUR...

STANDARD FOR DUST CONTROL

- DUST CONTROL MEASURES SHALL BE USED TO PREVENT BLOWING AND MOVEMENT OF DUST FROM EXPOSED SOIL SURFACES... 1. MULCH
A. SEE SPECIFICATIONS, THIS SHEET...
2. VEGETATIVE COVER
A. SEE SPECIFICATIONS, THIS SHEET...
3. SPRAY-ON ADHESIVES
A. ANIONIC ASPHALT EMULSION, DILUTED WITH WATER AT 7:1...
4. TILLAGE
A. ROUGHEN THE SURFACE TO BRING CLODS TO THE SURFACE...
5. SPRINKLING
A. SPRINKLE ALL EXPOSED AREAS UNTIL THE SURFACE IS WET...
6. BARRIERS
A. SOLID BOARD FENCE, SNOW FENCES, BURLAP FENCES...
7. CALCIUM CHLORIDE
A. LOOSE, DRY GRANULES OR FLAKES SHALL BE FED THROUGH COMMONLY USED SPREADERS...
8. STONE
A. COVER SURFACE WITH CRUSHED STONE OR COARSE GRAVEL...
9. MONITORING OF AREAS WHERE HIGH ACID PRODUCING SOIL HAS BEEN PLACED OR BURIED SHOULD BE PERFORMED FOR AT LEAST 2 YEARS OR LONGER IF PROBLEMS OCCUR...

STABILIZATION WITH MULCH

SEQUENCE OF CONSTRUCTION OPERATIONS

Table with 2 columns: OPERATION, TOTAL. Shows a total duration of 126 weeks (29 months) for the sequence of construction operations.

SOIL EROSION AND SEDIMENT CONTROL PLAN NOTES

MANAGEMENT OF HIGH ACID PRODUCING SOIL


STANDARD FOR DUST CONTROL

SEQUENCE OF CONSTRUCTION OPERATIONS


PERMANENT SEED MIX

Revision table with columns: Date, Description, Revisions, No. Includes a signature for Chris Roche, Professional Engineer NJ Lic. No. 240E04988100.

BRIDGE POINT 8 INDUSTRIAL PARK WEST WINDSOR TOWNSHIP MERCER COUNTY NEW JERSEY
Drawing Title: SOIL EROSION & SEDIMENT CONTROL DETAILS
Project No.: 130172801
Date: 12/03/2021
Checked By: EAW
Drawn By: CMR



CONSTRUCTION GATE



24" SILT FENCE



Material and Performance Specification Sheet

ECC-2 Double Net Coconut Rolled Erosion Control Product

Description: The ECC-2 is made with uniformly distributed 100% coconut fiber and two polypropylene nets securely woven together with UV stabilized thread. The tightly compressed blankets are placed inside vertical bags and include a product label, code and installation guide. The blankets are palletized for easy transportation.

The ECC-2 has functional longevity of approximately 36 months, but will vary depending on soil and climatic conditions and is suitable for slopes 1:1. The ECC-2 meets Type 4 specification requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) PP-63 Section 713.17.


Material:	Netting - Top and Bottom	Matrix	Thread
	Heavyweight UV Stabilized Polypropylene .75" x .75" Opening	100% Coconut Fiber 0.55 lbs/yd	UV Stabilized 1.50" stitch spacing

Roll Sizes:	Standards	Standards
Width: 7.5 ft (2.3 m)	56.0 ft (17.0 m)	7.5 ft (2.3 m)
Length: 48.0 lbs (21.4 kg)	48.0 ft (14.6 m)	68.0 lbs (30.8 kg)
Weight ±10%: 48.0 lbs (21.4 kg)	48.0 ft (14.6 m)	100 yd (91.4 m)
Area: 20	20	16

Index Value Properties:	Test Method	Typical	Test Method	Parameters	Results
Resilience Area	ASTM D5199	5-15 sq/ft	ECTC Method 2	150mm (6") / 10-30 min	SR**=48.09
Thickness	ASTM D5199	23 in.	ECTC Method 2	100mm (4") / 10-30 min	SR**=11.71
Tensile Strength-MD	ASTM D5035	270 lb/ft	ECTC Method 3	150mm (6") / 10-30 min	SR**=17.43
Flexion Mod	ASTM D5035	38 %	ECTC Method 3	Shear Resistance	Top soil Failure: 75% improvement
Tensile Strength-TD	ASTM D5035	170 lb/ft	ECTC Method 4	Germination	Top soil Failure: 21 day incubation
Flexion Mod	ASTM D5035	30 %	ECTC Method 4	Germination	Top soil Failure: 75% improvement
Light Penetration	ECTC Guidelines	14 %			
Water Absorption	ASTM D1117	233 %			

Design Values:	Value
Property	Value
Manning's N	.05
RISE C-Factor	.09
Maximum Permissible Shear Stress	3.2 psf (151 Pa)
Maximum Flow Velocity	7.0 ft/sec (2.13 m/sec)


NOTE: CONTRACTOR TO INSTALL PER MANUFACTURER'S RECOMMENDATIONS.



- Construction Specifications**
- Pit dimensions are variable, with the minimum diameter being 2 times the standpipe diameter.
 - The standpipe should be constructed by perforating a 12" to 24" diameter corrugated or PVC pipe. Then wrapping with 1/2" hardware cloth and geotextile fabric. The perforations shall be 1/2" x 6" slits or 1" diameter holes.
 - A base of filter material consisting of clean gravel or ASTM C33 stone should be placed in the pit to a depth of 12". After installing the standpipe, the pit surrounding the standpipe should then be backfilled with the same filter material.
 - The standpipe should extend 12" to 18" above the lip of the pit or the riser crest elevation (basin dewatering only) and the filter material should extend 3" minimum above the anticipated standing water elevation.

NOTE: ALL CONSTRUCTION DEWATERING TO BE IN CONFORMANCE WITH STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY, SIXTH EDITION, SECTION 14 AND APPLICABLE NJDEP PERMITS FOR THE PROJECT.

NEW JERSEY SOIL EROSION AND SEDIMENT CONTROL DETAIL FOR CONSTRUCTION DEWATERING




- NOTES:**
- DISTURBED AREAS SHALL BE MULCHED WITH STRAW OR HAY IF THE FALL SEEDING PERIOD CANNOT BE SUCCESSFULLY MET.
 - MULCH TO BE APPLIED AT A RATE OF 1.5 TO 2 TONS PER ACRE. TACK MATERIAL TO BE CUTBACK ASPHALT-RAPID CURING (RC-70, PC-250 AND RC-800) OR MEDIUM CURING (MC-250 OR MC-800). APPLY 0.4 GAL/S.Y. OR 194 GAL/ACRE ON FLAT AREAS AND ON SLOPES LESS THAN 8 FEET HIGH ON SLOPES 8 FEET OR MORE HIGH USE .075 GAL/S.Y. OR 363 GAL/ACRE.

6-FT TEMPORARY CONSTRUCTION FENCE


Table 29-1: Lengths of Construction Exits on Sloping Roadbeds

Percent Slope of Roadway	Length of Stone Required	Course-Grained Soils	Fine-Grained Soils
2 to 5%	100 ft.	200 ft.	
> 5%	Entire surface stabilized with Hot Mix Asphalt Base Course, Mix 1-2		

NOTE: FOR CONSTRUCTION PAD LOCATION SEE SOIL EROSION AND SEDIMENT CONTROL PLAN.




STABILIZED CONSTRUCTION ACCESS




- NOTES:**
- SEDIMENT FILTER BAGS ARE FOR USE WITH ALL INLETS THAT ARE IN PAVED AREAS BUT ARE NOT ADJACENT TO CURBING.
 - SEDIMENT FILTER BAGS SHALL BE MANUFACTURED BY SILTSACK (REGULAR FLOW MODEL) OR APPROVED EQUAL.
 - LENGTH AND WIDTH OF FILTER BAG VARIES ACCORDING TO INLET SIZE.
 - OVERFLOW HOLES ARE REQUIRED A MINIMUM OF 1 FOOT ABOVE THE BOTTOM OF THE BAG.

SEDIMENT FILTER BAG INSERT




PROBING WIRE TEST 15.5 GA. STEEL WIRE (SURVEY FLAG)

EROSION CONTROL BLANKET DETAIL



NOTE: SOIL SHOULD BE MOIST BUT NOT SATURATED. DO NOT TEST WHEN SOIL IS EXCESSIVELY DRY OR SUBJECT TO FREEZING TEMPERATURES. SLOW, STEADY DOWNWARD PRESSURE USED TO ADVANCE THE PROBE. MEASURE DEPTH WHEN GAGE READING REACHES 300 PSI OR DEPTH OF 6"


HANDHELD SOIL PENETROMETER TEST



NOTE: SOIL COMPACTION TESTING LOCATIONS IDENTIFIED ARE RECOMMENDED LOCATIONS FOR GRADED/DISTURBED AREAS WITHIN THE VICINITY OF BUILDINGS AND STRUCTURES OR ON INDIVIDUAL LOTS. FOR GRADED/DISTURBED AREAS WITHIN OPEN OR COMMON SPACES, SOIL COMPACTION TESTING SHALL BE PERFORMED IN ACCORDANCE WITH THE FREQUENCY LISTED IN THE LEGEND (THIS SHEET).

TYPICAL SOIL COMPACTION TESTING LOCATIONS

TEMPORARY SOIL STOCKPILE




ESTIMATE A TREE'S PROTECTED ROOT ZONE (PRZ) BY CALCULATING THE CRITICAL ROOT RADIUS (CRR).

- MEASURE THE DBH (DIAMETER OF TREE AT BREAST HEIGHT, 4.5 FEET ABOVE GROUND ON THE UPHILL SIDE OF TREE) IN INCHES.
- MULTIPLY MEASURED DBH BY 1.5 OR 1.0. EXPRESS THE RESULT IN FEET. CRR = DBH x 1.5. CRITICAL ROOT RADIUS FOR OLDER, UNHEALTHY, OR SENSITIVE SPECIES. CRR = DBH x 1.0. CRITICAL ROOT RADIUS FOR YOUNGER, HEALTHY, OR TOLERANT SPECIES.


- NOTES:**
- PROTECTIVE FENCE TO BE REMOVED AFTER CONSTRUCTION.
 - ALL EXPOSED ROOT STUBS AND ROOTS ARE TO BE BACK FILLED WITH APPROVED TOPSOIL.
 - REFER TO STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY - TABLE 9-1 FOR POTENTIAL CONSTRUCTION IMPACTS TO TREES SPECIES.

TREE PROTECTION



- NOTES:**
- STRAW BALE BARRIERS SHOULD NOT BE USED FOR MORE THAN 3 MONTHS.
 - STRAW BALE BARRIERS MUST BE PLACED AT LEVEL GRADES. BOTH ENDS OF THE BARRIER MUST BE EXTENDED AT LEAST 8 FEET UPSLOPE AT 45° TO MAINTAIN BARRIER ALIGNMENT.
 - SEDIMENT MUST BE REMOVED WHERE ACCUMULATIONS REACH 1/3 THE ABOVE GROUND HEIGHT OF THE BARRIER.
 - ANY SECTION OF STRAW BALE BARRIER WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. SEE ROCK FILTER OUTLET DETAIL.
 - BALES SHALL BE SECURELY ANCHORED IN PLACE BY TWO STAKES OR RE-TOWARDS DRIVEN THROUGH EACH BALE. THE FIRST STAKE IN EACH BALE SHALL BE DRIVEN TOWARD PREVIOUSLY LAID BALE TO FORCE BALES TOGETHER.
- MAINTENANCE:** INSPECT ONCE EVERY WEEK OR AFTER EVERY STORM EVENT. HAYBALE BARRIERS WILL BE REMOVED WHEN CLOGGED WITH SEDIMENTS. MATERIALS MUST BE WASHED COMPLETELY FREE OF ALL FOREIGN MATERIALS OR NEW HAYBALE BARRIERS MUST BE USED TO REBUILD THE BARRIER.


STRAW BALE BARRIERS



ID (FT)	Lo (FT)	W (FT)	d50 (INCHES)
HW-100	24	20	6 1/2" THICK
HW-200	9	7.5	6 1/2" THICK
HW-306	18	15	6 1/2" THICK
HW-400	18	14	6 1/2" THICK
HW-500	24	20	6 1/2" THICK
HW-600	13.5	12	6 1/2" THICK

* OVER FILTER FABRIC


PRE-FORMED SCOUR HOLE



- NOTES:**
- THE FLOATING RISER (SKIMMER) SHALL BE CONNECTED TO THE PERMANENT OUTLET CONTROL STRUCTURE USING A WATER TIGHT CONNECTION. AN ORIFICE PLATE SHALL BE PROVIDED TO BLOCK THE REMAINDER OF THE LOW FLOW ORIFICE.

FLOATING RISER DETAIL

ID	LENGTH (FT)	WIDTH (FT)	d50 (INCHES)
BASIN 1 SPILLWAY	75	10	6
BASIN 2 SPILLWAY	130	5	6



- GENERAL NOTES:**
- THE INDICATED 450' APRON LENGTH, WIDTH AND THICKNESS HAS BEEN DESIGNED IN ACCORDANCE WITH THE NEW JERSEY SOIL EROSION AND SEDIMENT CONTROL STANDARDS
 - DIMENSIONS SHOWN ARE MINIMUMS. CONTRACTOR MAY EXCEED DIMENSIONS WITH GABION BASKET/FROM MATTRESS UNITS.

CONDUIT OUTLET PROTECTION (RIP RAP)

Date	Description	No.
2/15/2022	Revised per Township Comments	2
12/3/2021	Completeness Revisions 1	1

REVISIONS

Chris Roche
SIGNATURE CHRISTIAN ROCHE 11/12/2021
PROFESSIONAL ENGINEER NJ Lic. No. 240E04988100

LANGAN
Langan Engineering and Environmental Services, Inc.
989 Lenox Drive, Suite 124
Lawrenceville, NJ 08648

T: 609.282.8000 F: 609.282.8001 www.langan.com
NJ CERTIFICATE OF AUTHORIZATION No. 24G04798460

BRIDGE POINT 8 INDUSTRIAL PARK

WEST WINDSOR TOWNSHIP

MERCER COUNTY NEW JERSEY

SOIL EROSION & SEDIMENT CONTROL DETAILS

Project No.	Drawing No.
130172801	CE502
Date	12/03/2021
Drawn By	
Checked By	